

Project Title: Garbutt State School – Athletics and Cricket Upgrade

Project No.: 34-165425

Tender No.: QED: 4957/2025

Location:



Scope:

GENERAL SCOPE OF WORK:

- Contractor to provide Form 15 and 16 Certification
- All design and construction documentation to be provided including warranties in the name of the school.
- Site preparation:
 - levelling of site
 - removal and disposal of turf, soil and construction waste.
 - Dial B4U Dig/ service relocation

- Hydrovac as required
- Site security
- Supply and installation of all play equipment
 - Freight
 - Installation
 - Site clean-up with all rubbish removed
- Investigate services underground around existing cricket nets and surrounding area of proposed works;

Cricket Nets:

- Remove existing cricket net system including concrete slabs.
- Provide new cricket net system consisting of the following:
 - 2 Lane Practice Cricket Wicket
 - Overall size 22m long x 8m wide
 - Lane netting (chain wire mesh) 3.6m high x 18m long
 - Roof netting (chain wire mesh) extending 12m from batter end
 - Netting system to be chain wire mesh fencing
 - Synthetic cricket grass 3.6m wide x 24m long (x2) for the cricket pitches

Oval Cricket Pitch:

- Remove existing cricket Pitch including concrete slab.
- Provide new cricket Pitch, located in the centre of the School Oval consisting of the following:
 - Installation of new centre cricket pitch 24m x 2.8m
 - Overall size 22m long x 8m wide
 - Synthetic grass adhesive stick to slab

Long Jump:

- Provide new Long Jump pit and run-up track, consisting of the following:
 - Installation of new 9m x 3m sand pit with ag drain geo fab layer and certified sand
 - 20m long x 12.m wide Rubberised running track provided on concrete slab

Storage Shed:

- Provide new 12m x 6m x 2.7m H prefabricated gable shed consisting of the following:
 - Concrete slab
 - 4x Roller Doors
 - Internal central dividing wall to form 2x separate storage areas
 - 2x Whirlybirds
 - LED lighting to new shed structure
 - Electrical services including GPO's and security
 - Water supply and hose cock
 - Decomposed granite to be levelled, compact to ensure no soft spots and self-draining.
 - Contractor to locate power and water services for new works.

Existing Site Photos:



Existing cricket nets



Existing cricket pitch