

**GENERAL NOTES**

- G1. ALL WORK & MATERIALS SHALL BE IN ACCORDANCE WITH THE DRAWINGS, THE SPECIFICATION, AND CURRENT RELEVANT AUSTRALIAN STANDARDS, THE BUILDING CODE OF AUSTRALIA AND OTHER STATUTORY REQUIREMENTS
- G2. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH THE ARCHITECTURAL & OTHER CONSULTANTS DRAWINGS, THE SPECIFICATION AND ALL OTHER WRITTEN INSTRUCTIONS THAT ARE ISSUED DURING THE COURSE OF THE WORKS
- G3. THE BUILDER SHALL CONFIRM ALL RELEVANT DIMENSIONS BEFORE COMMENCING CONSTRUCTION/FABRICATION
- G4. ALL DISCREPANCIES SHALL BE REFERRED TO THE ARCHITECT /ENGINEER FOR CLARIFICATION BEFORE PROCEEDING. NOTIFY THE ARCHITECT/ENGINEER OF ALL VARIATIONS ARISING FROM THE CLARIFICATION OF THE DISCREPANCY BEFORE PROCEEDING WITH THE WORKS
- G5. REFER TO ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS
- G6. DO NOT SCALE DRAWINGS
- G7. ALL DIMENSIONS ARE IN MILLIMETRES OR METRES UNLESS NOTED OTHERWISE
- G8. NO SUBSTITUTION SHALL BE MADE WITHOUT THE WRITTEN APPROVAL OF THE ENGINEER
- G9. THE BUILDER SHALL MAINTAIN THE WORKS IN A SAFE, STABLE CONDITION AND ENSURE THAT NO PART IS OVER-STRESSED DURING CONSTRUCTION
- G10. ALL PROPS AND FORMWORK TO A BEAM OR SLAB SHALL BE REMOVED BEFORE ANY MASONRY IS CONSTRUCTED ON THAT BEAM OR SLAB
- G11. ALL NON LOAD BEARING WALLS SHALL BE CONSTRUCTED 20mm CLEAR OF SLAB AND BEAM SOFFITS U.N.O
- G12. THE ENGINEER ACCEPTS NO RESPONSIBILITY FOR THE WORKS UNLESS THE WORKS ARE INSPECTED AND APPROVED BY THE ENGINEER DURING CONSTRUCTION
- G13. A MINIMUM OF 48 HRS NOTICE IS REQUIRED FOR ALL ENGINEERING INSPECTIONS U.N.O

**TIMBER NOTES**

- T1. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH AS1720 AND AS1884
- T2. STRUCTURAL TIMBER AS SHOWN ON THE ENGINEER'S DRAWINGS SHALL HAVE A MINIMUM STRESS GRADE AS BELOW U.N.O  

KILN DRIED HARDWOOD	KDHW	F17
LVL HYSYPAN	LVL	F16
UNSEASONED HARDWOOD	HW	F8
ORGON/TREATED PINE	T/PIPE	F5
SEASONED RADIIATA PINE	S/RP	F7
- T3. TIMBER SIZES NOT CALLED UP SHALL BE IN ACCORDANCE WITH AS1684 OR THE ARCHITECTURAL DRAWINGS. ANY DISCREPANCY SHALL BE REFERRED TO THE ARCHITECT/DESIGNER
- T4. ALL BOLTED CONNECTIONS SHALL USE OVER SIZED WASHERS UNDER BOLT HEAD AND NUT. ALL EXTERNAL BOLTS, NUTS AND WASHERS SHALL BE HOT DIPPED GALVANISED. NO KNOTS OR DEFECTS SHALL OCCUR WITHIN 150mm OF BOLT GROUP OR CONNECTORS. WHERE POSSIBLE RE-TIGHTEN BOLTS AFTER 6 WEEKS AND AGAIN AT 12 MONTHS
- T5. MAKE GOOD PRESERVATIVE TREATMENT WHERE CHECKOUTS, HOLES AND CUTS EXPOSE UNTREATED TIMBER
- T6. ALL EXTERNAL TIMBERS SHALL BE DURABLE, SUITABLE FOR EXTERNAL USE AND COMPLY WITH THE APPROPRIATE HAZARD LEVEL FOR SPECIFIC SERVICE CONDITIONS
- T7. GLUED LAMINATED BEAMS SHALL BE MANUFACTURED IN ACCORDANCE WITH AS1328. CAMBER SHALL BE AS NOTED ON THE DRAWINGS OR AS SPECIFIED. AND INSTALLED WITH HOG UP BEAMS FOR EXTERNAL USE SHALL BE FABRICATED USING RESORCINOL OR PHENOLIC ADHESIVE
- T8. ALL PROPRIETARY FIXINGS SHALL BE INSTALLED TO DEVELOP THEIR MAXIMUM CAPACITY AND IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS
- T9. ALL TIMBER FRAMEWORK SHALL BE ADEQUATELY TIED TO RESIST UPLIFT AND RACKING FORCES IN ACCORDANCE WITH AS1884
- T10. THE BUILDER SHALL SUBMIT ONE SET OF TRUSS MANUFACTURERS LAYOUT DRAWINGS & COMPUTATIONS FOR REVIEW PRIOR TO ORDERING ALL LINTELS/BEAMS & SUPPORTING STUDS
- T11. ANY DISCREPANCY IN TIMBER SIZES BETWEEN ARCHITECTURAL AND ENGINEERING DRAWINGS, SKETCHES OR COMPUTATIONS CONTACT ENGINEER FOR WRITTEN CLARIFICATION. OTHERWISE ENGINEERING SIZES OVERRULE ARCHITECTURAL SIZES

- T12. PREFABRICATED TIMBER ROOF & FLOOR TRUSSESS AND WALL FRAMING SHALL COMPLY WITH MANUFACTURERS DETAILS AND THE REQUIREMENTS OF AS1440
- S1. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH AS3600
- C1. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH AS3600 AS FOLLOWS U.N.O:  

SLABS-ON-GROUND	F <sub>c</sub> = 25 MPa
SLABS-ON-GROUND	F <sub>c</sub> = 25 MPa
PAVING SLABS	F <sub>c</sub> = 25 MPa
SUSPENDED CONCRETE	F <sub>c</sub> = 32 MPa
BLINDING CONCRETE	F <sub>c</sub> = 15 MPa
- C2. CONCRETE SHALL HAVE A CHARACTERISTIC COMPRESSIVE STRENGTH AS FOLLOWS U.N.O:  

SLABS-ON-GROUND	F <sub>c</sub> = 25 MPa
PAVING SLABS	F <sub>c</sub> = 25 MPa
SUSPENDED CONCRETE	F <sub>c</sub> = 32 MPa
BLINDING CONCRETE	F <sub>c</sub> = 15 MPa
- C3. CONCRETE SHALL BE CURED BY AN APPROVED METHOD FOR AT LEAST 7 DAYS AFTER PLACEMENT
- C4. CONCRETE SHALL BE COMPACTED USING MECHANICAL VIBRATION
- C5. VIBRATION OF FORMS IS NOT ACCEPTABLE AND CONCRETE SHALL NOT BE SPREAD BY VIBRATING
- C6. CONCRETE SECTIONS SHOWN ARE MINIMUM SIZES AND DO NOT INCLUDE FINISHES. SIZES SHALL NOT BE REDUCED IN ANY WAY OR HOLES FORMED OR MADE IN ANY MEMBER WITHOUT THE APPROVAL OF THE ENGINEER
- C7. DEPTH OF BEAMS ARE GIVEN FIRST AND INCLUDE SLAB THICKNESS
- C8. SLABS AND BEAMS ARE TO BE POURED TOGETHER U.N.O
- C9. MINIMUM COVER (mm) TO ALL REINFORCEMENT SHALL BE AS FOLLOWS U.N.O:  

COLUMNS & PEDESTALS	25
BEAMS	30
FOOTINGS	50
SLABS	25
- C10. REINFORCEMENT IS SHOWN DIAGRAMATICALLY AND NOT IN TRUE PROJECTION
- C11. SYMBOLS ON THE DRAWING FOR REINFORCEMENT ARE AS FOLLOWS:  

S1 - HARD DRAWN DEFORMED GRADE 550 MPa STEEL WIRE REINFORCING FABRIC TO AS4671	
N - GRADE 500 MPa DEFORMED REINFORCING BARS TO AS4671	
R - GRADE 250 MPa PLAIN REINFORCING BARS TO AS4671	
S - STRUCTURAL GRADE DEFORMED BARS TO AS4671	
M - HARD DRAWN STEEL WIRE REINFORCING WIRE TO AS4671	
TH - HARD DRAWN STEEL TRENCH MESH TO AS4671	
- C12. ALL REINFORCEMENT AND INSERTS SHALL BE SUPPORTED AND HELD IN THE DESIGN LOCATION BY APPROVED CHAIRS, SPACERS OR TIES. BAR CHAIRS SHALL BE PLACED AT MINIMUM 1000 CRS IN TWO DIRECTIONS U.N.O
- C13. WELDING AND THREADING OF REINFORCEMENT IS NOT PERMITTED WITHOUT THE APPROVAL OF THE ENGINEER
- C14. REINFORCEMENT SHALL BE EVENLY DISTRIBUTED OVER THE WIDTHS SHOWN U.N.O
- C15. AT SLAB EDGES INCLUDING CONSTRUCTION AND OTHER JOINTS AT LEAST ONE REINFORCING BAR OF FABRIC WIRE SHALL BE LOCATED PARALLEL TO AND WITHIN 75mm OF THE SLAB EDGE
- C16. CONSTRUCTION JOINTS SHALL BE PROPERLY FORMED AND USED ONLY WHERE APPROVED OR PERMITTED BY THE ENGINEER
- C17. SAWN JOINTS SHALL BE MADE AT A TIME APPROPRIATE TO THE CONCRETE MIX AND CLIMATIC CONDITIONS - GENERALLY WITHIN 10 & 20 HOURS OF PLACING THE CONCRETE
- C18. STRIPPING OF FORMS AND REMOVAL OF FORMWORK SHALL TAKE PLACE IN ACCORDANCE WITH A PROCEDURE AGREED WITH THE ENGINEER
- C19. CONCRETE MUST BE SEPERATED FROM SUPPORTING BRICKWORK BY TWO LAYERS OF SUITABLE DEBONDING MEMBRANE, I.E. MALTROID OF 3mm PER 1000mm. BEAMS SHALL BE CAMBERED AS SHOWN ON DRAWINGS
- C20. SUSPENDED SLABS SHALL BE GIVEN AN UPWARD MID SPAN CAMBER OF 3mm PER 1000mm. BEAMS SHALL BE CAMBERED AS SHOWN ON DRAWINGS
- C21. SPLICES IN REINFORCEMENT SHALL BE MADE IN THE POSITIONS SHOWN ON THE DRAWINGS OR AS OTHERWISE APPROVED BY THE ENGINEER
- C22. HOLDING DOWN BOLTS SHALL BE SUPPLIED TO THE CONCRETOR FOR CASTING INTO THE CONCRETE AND SHALL BE INSTALLED IN ACCORDANCE WITH THE STEEL HOLDING DOWN BOLT PLAN SUPPLIED BY STEEL FABRICATOR
- C23. STRIPING OF FORMS AND REMOVAL OF FORMWORK SHALL TAKE PLACE IN ACCORDANCE WITH A PROCEDURE AGREED WITH THE ENGINEER
- C24. CONCRETE MUST BE SEPERATED FROM SUPPORTING BRICKWORK BY TWO LAYERS OF SUITABLE DEBONDING MEMBRANE, I.E. MALTROID OF 3mm PER 1000mm. BEAMS SHALL BE CAMBERED AS SHOWN ON DRAWINGS
- C25. ALL WELDS SHALL BE CONTINUOUS FILLET WELD. SIZE 6mm. GP CATEGORY USING EX1XX/40X CONSUMABLES U.N.O
- C26. ALL WELDING SHALL BE IN ACCORDANCE WITH AS1554
- C27. HOLDING DOWN BOLTS SHALL BE M16@ 8.0/S. GALVANISED U.N.O
- C28. CONNECTIONS NOT SPECIFICALLY DETAILED SHALL BE IN ACCORDANCE WITH THE APPROPRIATE CONNECTIONS DETAILED IN AISC STANDARDISED STRUCTURAL CONNECTIONS MANUAL
- C29. ALL CLEAT PLATES AND STIFFENERS SHALL BE 10mm THICK U.N.O
- C30. THE ENDS OF TUBULAR MEMBERS SHALL BE SEALED WITH A 8mm PLATE & 6mm CPW U.N.O
- C31. TUBULAR MEMBERS TO BE GALVANISED SHALL BE ADEQUATELY VENTED
- C32. PURLINS AND GRIS SHALL BE IN ACCORDANCE WITH AS/NZS 4600 GALVANISED AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS
- C33. BEFORE COMMENCING FABRICATION COPIES OF THE SHOP DRAWINGS SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW. THIS REVIEW DOES NOT REMOVE THE RESPONSIBILITY FOR THE INTERPRETATION OF THE DRAWINGS, DIMENSIONAL ACCURACY AND THE STEEL FABRICATION FROM THE STEEL FABRICATOR/BUILDER

- S14. MINIMUM CAMBER TO BE 3mm PER METER LENGTH OF STEEL BEAMS OR AS NOTED ON THE DRAWINGS
- S15. STRUCTURAL STEEL TO BE CONCRETE ENCASED SHALL BE WRAPPED WITH S14.1 MESH. THE GAP BETWEEN THE STRUCTURAL STEEL AND THE MESH AND THE EXTERNAL COVER TO THE MESH TO BE 25mm AND 50mm RESPECTIVELY
- S16. ALL BOLTS AND STRUCTURAL STEEL EXPOSED TO THE WEATHER TO BE HOT DIPPED GALVANISED U.N.O
- S17. ALL STEEL LINTELS SUPPORTING MASONRY EXPOSED TO WEATHER TO BE HOT DIPPED GALVANISED U.N.O
- S18. ALL STEELWORK BELOW GROUND SHALL BE ENCASED IN 75mm CLEAR COVER OF 20MPa CONCRETE U.N.O
- S19. ALL STEELWORK SHALL BE WIRE BRUSHED TO AS4672 AND PAINTED WITH ONE SHOP COAT OF APPROVED ZINC RICH PRIMER. U.N.O MEMBERS ENCASED IN CONCRETE, FIRE SPRAYED OR FRICTION GRIP BOLTED CONNECTIONS NOT TO BE PAINTED
- S20. CONTRACTOR/BUILDER RESPONSIBLE FOR TEMPORARY BRACING AS REQUIRED TO STABILISE THE STRUCTURE DURING ERECTION UNTIL PERMANENT BRACING ELEMENTS ARE CONSTRUCTED
- MASONRY
- M1. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH AS3700
- M2. MORTAR FOR GENERAL MASONRY CONSTRUCTION SHALL CONSIST OF 1 CEMENT, 1 HYDRATED LIME & 6 WELL GRADED SAND UNLESS OTHERWISE REQUIRED BY AS3700
- M3. MASONRY TIES FOR CAVITY WALLS SHALL BE MEDIUM DUTY CLASSIFICATION SPACED AT NOT MORE THAN 600 CENTRES VERTICALLY AND HORIZONTALLY. ADDITIONAL TIES SHALL BE PLACED ADJACENT TO LATERAL SUPPORTS. CONTROL JOINTS AND AROUND OPENINGS AT A SPACING OF NOT MORE THAN 300, AND LOCATED NOT MORE THAN 300 FROM THE LINE OF SUPPORT.
- M4. MASONRY SHALL BE TIED TO COLUMNS AT 400 MAXIMUM VERTICAL CENTRES
- M5. ALL CAVITIES BELOW GROUND LEVEL SHALL BE MORTAR OR GROUT FILLED
- M6. VERTICAL CONTROL JOINTS SHALL COMPLY WITH TECHNICAL NOTE NO. 61 PUBLISHED BY THE CEMENT & CONCRETE ASSOCIATION OF AUSTRALIA. CEMENT AND SHALL BE LOCATED AS DESCRIBED IN THAT PUBLICATION OR AS SHOWN ON THE ARCHITECTURAL DRAWINGS CONTROL JOINT SPACING SHALL NOT EXCEED 6.0m
- REINFORCED MASONRY
- R1. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH AS3700
- R2. MORTAR TO CLAY MASONRY SHALL CONSIST OF 1 CEMENT, 1/4 HYDRATED LIME, 3 WELL GRADED SAND. CAVITY GROUT SHALL CONSIST OF 1 CEMENT, 2 & 1/2 SAND, 1 & 1/2 10mm AGGREGATE
- R3. THERE SHALL BE A MINIMUM OF 150mm COVER OF GROUT AROUND ALL REINFORCEMENT
- R4. THE TWO SKINS OF MASONRY SHALL BE BONDED TOGETHER WITH HEAVY DUTY MASONRY TIES AT MAXIMUM 600 CENTRES
- R5. CLEAN OUT PORTS SHALL BE PROVIDED FOR EACH POUR BY LEAVING OUT TWO UNITS AT THE BOTTOM OF EACH SECTION TO BE GROUTED. DURING WORK, MORTAR FINS AND ANY OTHER MATERIAL SHALL BE REMOVED FROM THE CAVITY GROUT SPACE. THE PORTS SHALL BE SEALED WITH SIMILAR MASONRY UNITS AFTER INSPECTION AND BEFORE GROUTING
- R6. THE REINFORCEMENT CAVITY SHALL BE NOT LESS THAN 75mm IN WIDTH U.N.O
- R7. MORTAR SHALL CURE FOR THREE DAYS BEFORE POURING CAVITY GROUT
- R8. CAVITY GROUTING SHALL BE DONE IN LIFTS NOT EXCEEDING 300mm PER 12 HOUR PERIOD AND RODED INTO POSITION
- SITE WORKS AND SITE MAINTENANCE
- W1. ADEQUATE DRAINAGE SHALL BE PROVIDED TO PREVENT WATER PONDING OR COLLECTING ADJACENT TO THE WORKS
- W2. TRENCHES UNDER OR ADJACENT TO THE WORKS SHALL BE BACKFILLED WITH COMPACTED CLAY OR CONCRETE
- W3. TRENCHES PARALLEL TO THE EDGE OF THE STRUCTURE SHALL BE OFFSET A DISTANCE AT LEAST EQUAL TO THE DEPTH OF THE TRENCH EXCAVATION
- W4. ROOF GUTTERS, DOWNPIPES, STORMWATER AND SEWERAGE DRAINAGE SHALL BE MAINTAINED TO PREVENT OVERFLOWS. ANY LEAKS SHALL BE PROMPTLY REPAIRED
- W5. THE PLANTING OF TREES AND LARGE SHRUBS AND GENERAL SITE MAINTENANCE SHALL COMPLY WITH THE REQUIREMENTS OF AS2870 AND CSIRO PUBLICATION SHEET 'BT16 FOUNDATION MAINTENANCE AND FOOTING PERFORMANCE - A HOMEOWNERS GUIDE'. IT IS THE BUILDERS RESPONSIBILITY TO ENSURE THAT THE OWNER IS INFORMED OF THESE REQUIREMENTS
- DRAINAGE (ADDITIONAL REQUIREMENTS FOR CLASSES M, H1, H2 & E SITES
- D1. SURFACE DRAINAGE OF THE SITE SHALL BE CONTROLLED FROM THE START OF SITE PREPARATION AND CONSTRUCTION. THE DRAINAGE SYSTEM SHALL BE COMPLETED BY THE FINISH OF CONSTRUCTION.
- D2. THE BASE OF TRENCHES SHALL BE SLOPED AWAY FROM THE BUILDING. TRENCHES SHALL BE BACKFILLED WITH CLAY IN THE TOP 300mm WITH 15m OF THE BUILDING. THE CLAY USED FROM BACKFILLING SHALL BE COMPACTED. WHERE PIPES PASS UNDER THE FOOTING SYSTEM, THE TRENCH SHALL BE BACKFILLED FULL DEPTH WITH CLAY OR CONCRETE TO RESTRICT WATER INGRESS.
- D3. WHERE PIPES PASS UNDER THE FOOTING SYSTEM, THE TRENCH SHALL BE BACKFILLED FULL DEPTH WITH CLAY TO ACT AS A BARRIER TO THE INGRESS OF WATER BENEATH THE FOOTING SYSTEM. ALTERNATIVELY A PLASTIC MEMBRANE ACROSS THE CROSS-SECTION OF THE TRENCH TAPED TO THE PIPE AND KEVED INTO THE SIDES AND BASE OF THE TRENCH MAY BE USED.
- D4. SUBSURFACE DRAINS TO REMOVE GROUNDWATER SHALL NOT BE USED WITHIN 15m OF THE BUILDING UNLESS DESIGNED BY AN ENGINEER

**DRAWING LIST**

- S1 NOTESHEET & DRAWING LIST
- S2 FOOTING PLAN
- S3 ROOF FRAMING PLAN

A	09/10/24	FIRST ISSUE
REV	DATE	DESCRIPTION

**G C GEBERT**  
CONSULTING ENGINEERS PTY LTD  
CIVIL AND STRUCTURAL ENGINEERS

1/1449 POINT NEPEAN ROAD  
PO BOX 560 ROSEBUD, VICTORIA 3039

P. 0359 812902 M. 0448 444 151 E. eng@gcgeberb.com.au

PROJECT  
PROPOSED ADDITIONS  
38 VALLEY DRIVE, RYE

CLIENT  
TAYLOR


DRAWING  
NOTESHEET & DRAWING LIST

DRAWN	CHKD	DATE	SCALE	PROJECT NO.	DWG NO.	REV.
CL		OCT'24	1:100	G8805	S1	A

TIMBER FRAMING & BRACING IN ACCORDANCE WITH AS1684  
'RESIDENTIAL TIMBER FRAMED CONSTRUCTION'


ALL EXPOSED STEEL TO BE HOT DIPPED GALVANISED  
ALL EXPOSED TIMBER TO BE TREATED OR DURABLE SPECIES  
SITE CLASSIFICATION ASSUMED CLASS 'S' - STABLE ALL SAND  
TO BE CONFIRMED ONSITE BY BUILDER  
CONCRETE MIN. STRENGTH 25 MPa FOR SLABS & FOOTINGS

FOOTING SCHEDULE	
MARK	DESCRIPTION & REMARKS
P1	600 $\phi$ x 1250 MIN. DEEP CONCRETE PAD FOOTING SUPPORTING CYPRESS POST OVER FOUND MIN. 100 INTO NATURAL MEDIUM DENSE SAND



## FOOTING PLAN

SCALE 1:100



## PAD P1 TYPICAL DETAIL

SCALE 1:20

REV	DATE	DESCRIPTION
A	09/10/24	FIRST ISSUE



**G C GEBERT**  
CONSULTING ENGINEERS PTY LTD  
CIVIL AND STRUCTURAL ENGINEERS  
1/1449 POINT NEPEAN ROAD  
PO BOX 560 ROSEBUD, VICTORIA 3939

P: 0359 812902 M: 0448 444 151 E: eng@gcgeber.t.com.au


PROJECT  
PROPOSED ADDITIONS  
38 VALLEY DRIVE, RYE

CLIENT  
TAYLOR

DRAWING  
FOOTING PLAN

DRAWN	CHKD	DATE	SCALE	PROJECT NO.	DWG NO.	REV.
CL		OCT'24	1:100	G8805	S2	A



TIMBER FRAMING & BRACING IN ACCORDANCE WITH AS1684  
 'RESIDENTIAL TIMBER FRAMED CONSTRUCTION'  
 ALL EXPOSED STEEL TO BE HOT DIPPED GALVANISED  
 ALL EXPOSED TIMBER TO BE TREATED OR DURABLE SPECIES  
 DESIGNED FOR ULTIMATE WIND SPEED - 45 m/s (Vult)



## ROOF FRAMING PLAN

SCALE 1:100

MEMBER SCHEDULE	
MARK	DESCRIPTION & REMARKS
R1	2/290 x 4.5 F27 MERBEAU OR SIMILAR F27 STEEL OPTION - 180 PFC 1250 MAX CANTILEVER, 5400 BACKSPAN
R.T	ROOF TRUSSES @ 900 CRS TO MANUFACTURERS DESIGN
PT	200 x 200 CYPRESS POST



## R1 TOP PT

SCALE 1:20

REV	DATE	DESCRIPTION
A	09/10/24	FIRST ISSUE



**G C GEBERT**  
 CONSULTING ENGINEERS PTY LTD  
 CIVIL AND STRUCTURAL ENGINEERS  
 1/1449 POINT NEPEAN ROAD  
 PO BOX 560 ROSEBUD, VICTORIA 3939

P: 0359 812902 M: 0448 444 151 E: eng@gcgeber.t.com.au

PROJECT  
 PROPOSED ADDITIONS  
 38 VALLEY DRIVE, RYE

CLIENT  
 TAYLOR

DRAWN	CHKD	DATE	SCALE	PROJECT NO.	DWG NO.	REV.
CL		OCT'24	1:100	G8805	S3	A

DRAWING  
 ROOF FRAMING PLAN