

PACKING LIST			
CUSTOMER DETAILS:		DELIVERY ADDRESS:	
		Melbourne	
DESCRIPTION OF GOODS: Pre-Fabricated Steel Shed			
<u>1 off - 15m span x 50m long x 6m high Shed</u>			
22	columns x 6,000m (8 with cross bracings)	305x102x25 kgs/m	I-Beams
22	rafters x 7,607m (8 with cross bracings)	200x100x18 kgs/m	I-Beams
2	bundle purlins (2 bundles per shed) (12 x 10,250m) } (4 x 5,500m) } per bundle	125x75x20x2,0 (pre-galv)	Lipped Channel
		125x75x20x2,0 (pre-galv)	Lipped Channel
3	bundles purlins (3 bundles per shed) (12 x 10,000m)	125x75x20x2,0 (pre-galv)	Lipped Channel
1	bundle of cross bracings (8 column bracings x 7,700m) } (8 rafter bracings x 6,000m) } (1 bundle per shed) (8 rafter bracings x 6,800m) }	16mm dia Round Bar	16mm dia Round Bar
		16mm dia Round Bar	16mm dia Round Bar
1	bundle of knee bracings x 565mm long (120 per bundle) (1 bundle per shed)	40x40x3	Angle Iron
1	bundle bridging (20 x 1,489m per bundle)	40x40x3	Angle Iron
		(1 bundle per shed)	
Weight: 10 150 kgs			
COLOUR : PURPLE & PINK			
RECEIVED THE ABOVE ITEMS IN GOOD ORDER AND CONDITION:			
DATE:			
SIGNATURE:		NAME:	
CUSTOMER PLEASE NOTE:			
1.) OWNERSHIP IN GOODS DOES NOT PASS UNTIL PAYMENT HAS BEEN RECEIVED IN FULL, INCLUDING VAT.			
2.) WE WILL ONLY ACCEPT NOTIFICATION OF SHORTAGES WITHIN 24 HOURS OF ABOVE DELIVERY, FAILING WHICH THE LOAD WILL BE DEEMED COMPLETE.			

COLUMN CROSS BRACING CHECKED

RAFTER CROSS BRACING CHECKED

RAFTER GABLE CLEATS CHECKED

Checked By
Toy

Checked By
Jacques
